BANGALORE DIVISION.

Dated 27th August 1904.

1. Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 10th September 1904, for constructing Out-houses to the Agricultural and Bacteriological Laboratories at Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1905.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Out-houses to the Agricultural and Bacteriological Laboratories"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Constructing Out-houses to the Agricultural and Bacteriological Laboratories at Bangalore.

No.	Items of work.	Per.	Quantity.
	Constructing Out-houses to the Agricultural Laboratory.		
1	Earthwork excavation and filling	C. yd.	229
2	Stone in chunam, foundation and basement	C. ft.	7,605
3	Do superstructure	"	7,498
4	Burnt brick in chunam do	"	3,759
5	Chunam plastering	Sqr.	131·05
6	Chunam pointing	"	59·96
7	White-washing	"	131·05
8	Archwork stone in chunam	C. ft.	221
9	Do brick do	"	78
10	Stone slabs dressed	S. ft.	10·95
11	Honneywood work	C. ft.	321
12	Teakwood work including wood oiling	"	155
13	Roofing with Mangalore tiles, teak reepers, ridge tiles, etc., complete.	Sqr.	57·27
14	Terrace puckka	"	6·10
15	Ventilating tiles	No	38
16	Teakwood frame with zinc shutters, etc., complete ...	S. ft.	417
17	Do pannelled door	"	126
18	Do windows with iron bars, glazed shutters, etc., complete.	"	89
19	Teakwood battened door	"	212
20	Do windows with iron bars, etc., complete	"	315
21	Do ventilators with iron bars, etc., complete ...	"	25
22	Finials of iron	No.	6
23	Painting doors and windows, etc.	Sqr.	23·68
24	Zinc sheets	S. ft.	160
25	Parapet wall with brick in chunam, etc., complete	R. ft.	68
26	Cornice 9" thick	"	570
27	Cornice 3" thick	"	40
28	Flooring with asphalte over 3" concrete	Sqr.	2·41
29	Do Cuddapah slabs over 3" concrete and cement pointing.	"	18·55
30	Flooring with gravel	C. yd.	64

No.	Items of work.	Per.	Quantity.
	Constructing Out-houses to the Bacteriological Laboratory at Bangalore.		
	MAIN BUILDING.		
1	Earthwork	C. yd.	162
2	Stone in chunam, foundation and basement	C. ft.	8088
3	Do superstructure	,,	9212
4	Archwork stone in chunam	,,	19
5	Stone slabs dressed	S. ft.	512
6	Chunam pointing	Sqr.	141·18
7	Coping with burnt brick in clay and chunam plastering ...	R. ft.	15
8	Teakwood battened doors	S. ft.	350
9	Do gate with zinc sheets	,,	80
10	Do windows with iron bars, etc., complete	,,	106
11	Honneywood work	C. ft.	294·24
12	Providing cup boards with locks and keys, etc.	S. ft.	80
13	Zinc sheets under valley and hips	R. ft.	60
14	Roofing with 1st class Mangalore tiles and ridge tiles, teak reepers, etc., complete.	Sqr.	46·75
15	Ventilating tiles	No.	24
16	Eave boards	R. ft.	430
17	Finials	No.	3
18	Painting to doors and windows	Sqr.	10·74
19	Gate pillars	No.	2
20	Teakwood gate shutters	S. ft.	60
21	Flooring with stone slabs	Sqr.	9·71
22	Flooring with gravel	C. yds.	10
23	Filling earth to the basement level	C. ft.	22·79
24	Providing chimney	Lump sum Rs.	
25	Providing water tap in rooms	Do	
26	Teak frames with perforated trellies work	S. ft.	258
27	Flooring with Cuddapah slabs over 3" concrete and cement pointing.	Sqr.	12·08
	Quarters for Syces.		
1	Earthwork	C. yds.	33
2	Stone in chunam	C. ft.	3,017
3	Burnt brick in chunam	,,	1,816
4	Chunam plastering	Sqr.	25·63
5	Stone slabs dressed	S. ft.	144
6	White-washing	Sqr.	15·32
7	Colour-washing	,,	10·31
8	Roofing with 1st class Mangalore tiles, teak reepers, etc., complete.	,,	8·58
9	Ridging	R. ft.	39
10	Ventilating tiles	No.	6
11	Teakwood battened doors	S. ft.	68
12	Do windows with iron bars	,,	60
13	Honneywood work	C. ft.	49·66
14	Painting	Sqr.	2·56
15	Chunam pointing	,,	1·56
16	Flooring with stone slabs	,,	3·60
17	Eave boards	R. ft.	1·22
18	Earth filling	C. ft.	327
	Providing two Ranges of Harbury's Patent privy for Syces.		
1	Removing and refixing the present Harbury's privy with asphalte floor.	Lump sum Rs.	
	Surface Drainage.		
1	V. Slabbed drain ($1\frac{1}{2}' \times 1\frac{1}{2}'$)	R. ft.	200
	Opening out a gravel walk from Laboratory to the Out-house.		
1	Picking and forming road surface	S. yd.	318
2	Collecting, carting and consolidating gravel	C. yd.	15
3	Earthwork including carting	,,	848
4	Removing bushes and trees	Lump sum Rs.	
5	Sloping the platform	Do	
6	Turfing the slopes	Sqr.	5·00
7	Constructing range of steps and parapet at sides	Lump sum Rs.	
8	Metalling the surface over platform	C. yd.	23
	Wire fencing for enclosing Bacteriological and Geological Laboratory.		
	As per details in the body of the estimates	Lump Sum Rs	

B. S. VENKATACHARIAR, *Executive Engineer*